Stream Restoration Crediting for Meeting Sediment and Nutrient Goals in the Chesapeake Bay





Summary of 6-Month
Test Drive Results

Bill Stack



September 8, 2014

Stream Restoration Protocol Revisions

- WQGIT approved initial Protocols on May 13th 2013
- Presented 6-month test drive changes to WQGIT at May 12th 2014 meeting
- WQGIT wanted more time to review especially Technical Appendix
- USWG approved revisions on January 17th 2014
- WTWG approved revisions on August 28th 2014

Main Concerns Identified during the "Test-Drive" Review Process

General Concerns

- The default rate could conceivably lead to load reductions that can exceed watershed loading rates and may preclude the use of protocols 1 3.
- Found mistake for TN and TSS and made corrections.
- Added "the WTWG recommended that the aggregate load reductions from a practice should not exceed estimated loads in the Watershed Model for any given land-river segment."
- Confusion over application of the sediment delivery ratio and how it is applied to nutrients.
- Sediment delivery ratio integrated into interim rate and Protocol 1 for coastal plain (0.061) and non coastal plain (0.181)
- There are currently no mechanisms in the CBWM to adjust model parameters to account for enhanced instream nutrient uptake and/or denitrification associated with stream restoration.
- The WTWG recommended the Chesapeake Bay Program develop estimates of nutrient attenuation in small streams prior to calibration of the Phase 6 Watershed Model.

Main Concerns Identified during the "Test-Drive" Review Process

Protocol 1 Concerns

- The BANCS method may not be accurate and regional curves have not been developed.
- Gave jurisdictions flexibility to use alternative methods
- The 50% efficiency requirement is too low.
- Allowed for higher credit if supported by monitoring

Protocol 2 Concerns

- Certain types of projects result in load reductions that can exceed watershed loading especially for Protocol 2.
- Added "WTWG recommended the 40% cap be placed on total nitrate loads entering the stream for any given land-river segment rather than total nitrogen loads as denitrification only impacts nitrate.

Protocol 3 Concerns

- The curves used to develop Protocol 3 are not accurate enough for design purposes.
- Confusion over how upstream BMPs will affect load to the project and subsequently the credit received.
- Runoff reducing BMPs already accounted for in design.
- Recommendations for verification include accounting for upstream BMPs implemented